

PRELIMINARY MAINTENANCE WORKS:**IRR-PMW-2-11**

Providing and fixing 20 x 20 x 75 cm size temporary bench mark stone in CC 1 : 4 : 8

Data: **RATE ANALYSIS** UNIT : **10.00** Nos.**A. MATERIALS:**

SI No	particulars	Unit	Quantity	Rate	Amount
				in Rs.	in Rs.
1	Rough stone 20x20x75 cm	Each	10.00	49.00	490.00
2	Cement for CC & top finishing	kg	91.00	5.10	464.10
3	Coarse aggregate 40-20 mm	cum	0.25	1107.00	276.75
4	Sand (Un-Screened)	cum	0.25	777.00	194.25
Total cost of Materials				Rs:	1609.60

B. MACHINERY:

SI No	Description	Unit	Quantity	Rate	Amount
				in Rs.	in Rs.
1	NIL		0.00	0.00	0.00
Total hire charges of Machinery				Rs:	0.00

C. LABOUR:

SI No	Description	Unit	Quantity	Rate	Amount
				in Rs.	in Rs.
1	work inspector	Day	1.00	845.00	845.00
2	Stone chiseller Cl- I	Day	3.00	755.00	2265.00
3	mazdoor	Day	4.00	635.00	2540.00
Total cost of Labour				Rs:	5650.00

labour component/unit qty 565.00
 13.615% 76.92
 labour component/unit qty (including contractor's profit) **641.92**

ABSTRACT:

A. Cost of Materials		Rs:	1609.60
B. Hire charges of Machinery		Rs:	0.00
C. Cost of Labour		Rs:	5650.00
	Total	Rs:	7259.60
D. Add for contractor's profit and overheads on (A+B+C)	13.615%	Rs:	988.40
Total cost for	10.00 Nos.	Rs:	8248.00
Rate per Nos.	(A+B+C+D)/10	Rs.	824.80

LEAD ADDITIONS:

SI No	Material / Lead Details	Unit	Quantity	Rate	Amount
				in Rs.	in Rs.
Rate of Lead after removing included Initial Lead			Rs 245.00/cum		
1	Sand from approved quarry [15 km]	cum	0.25	245.00	61.25
Base final amount				Rs:	8248.00
Add Lead/Lift total				Rs:	61.25
Final amount with Lead				Rs:	8309.25
Rate per unit with Lead				Rs:	830.93