

IRR-CCDW-1-2**Canal and Cross Drainage Works- 2025-26**

PUBLISHED SUPABASE RECONSTRUCTION

Earth work in excavation **in all kinds of soils** of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material. **Depth upto 3 m** Unit = cum

DATA:	RATE ANALYSIS	UNIT: 240.00 CUM
--------------	----------------------	-------------------------

A. MATERIALS:

SI No	Particulars	Unit	Quantity	Rate in Rs.	Amount in Rs.
1	NIL		0.00	0.00	0.00
Total cost of Materials				Rs:	0.00

B. MACHINERY:

SI No	Description	Unit	Quantity	Rate in Rs.	Amount in Rs.
1	Hydraulic excavator 1.0 cum bucket capacity	hour	6.00	1,827.70	10,966.20
2	Fuel/ Energy charges	hour	6.00	1,447.50	8,685.00
Total hire charges of Machinery				Rs:	19,651.20

C. LABOUR:

SI No	Description	Unit	Quantity	Rate in Rs.	Amount in Rs.
1	Mazdoor (Unskilled)	day	12.00	550.00	6,600.00
2	Bhisthi (Waterman)	day	2.00	550.00	1,100.00
Total cost of Labour				Rs:	7,700.00

labour component/unit qty		32.08
Add contractor's profit and overhead charges 13.615%	13.615%	4.37
labour component/unit qty (including contractor's profit)		36.45

ABSTRACT:

A. Cost of Materials		Rs:	0.00
B. Hire charges of Machinery		Rs:	19,651.20
C. Cost of Labour		Rs:	7,700.00
	Total	Rs:	27,351.20
D. Add for contractor's profit and overheads on (A+B+C)	13.615%	Rs:	3,723.87
Total cost for	240.00 cum	Rs:	31,075.07
Rate per cum	(A+B+C+D)/240.00	Rs:	129.50