

TELANGANA IRRIGATION & CAD DEPARTMENT
RATE ANALYSIS (DATA BOOK)

SSR CODE: IRR-DAW-01 · UNIT: cum
Plain Cement Concrete 1:2:4 using 20mm HBG metal including vibrating, curing etc. complete.

S.No	Description	Quantity	Unit	Rate (Rs)	Amount (Rs)
I. MATERIALS					
1	Cement 43 Grade	0.32	MT	6,500.00	2,080.00
2	Coarse Sand (Zone II)	0.45	cum	850.00	382.50
3	HBG Stone Aggregate 20mm	0.90	cum	1,450.00	1,305.00
Materials Sub-Total:					3,767.50
II. LABOUR					
1	Mason 1st Class	0.30	day	850.00	255.00
2	Mazdoor (Unskilled)	2.20	day	550.00	1,210.00
3	Bhisthi (Waterman)	0.50	day	550.00	275.00
Labour Sub-Total:					1,740.00
Basic Cost for 1.00 cum:					5,507.50
Contractor Overhead & Profit (14%):					771.05
Lead Conveyance for Sand (15 km):					180.00
Total Rate per 1.00 cum:					Rs. 6,458.55