

RATE ANALYSIS (DATA BOOK)

Construction of High Level Bridge at Ch. 12+500

Standard Schedule of Rates (SOR: 2024-25)

SSR CODE: IRR-DAW-01 · UNIT: cum · OUTPUT: 1 cum	RATE / CUM
A. EARTH WORK EXCAVATION & EMBANKMENTS	Rs. 7,370.47
Plain Cement Concrete 1:2:4 nominal mix using 20mm HBG stone aggregate mechanically mixed and vibrated.	

S.No	Description	Quantity	Unit	Rate (Rs)	Amount (Rs)
I. MATERIALS					
1	Cement 43 Grade	0.32	MT	6,500.00	2,080.00
2	Coarse Sand (Zone II)	0.45	cum	850.00	382.50
3	HBG Stone Aggregate 20mm	0.90	cum	1,450.00	1,305.00
Materials Sub-Total:					3,767.50
II. LABOUR					
1	Mason 1st Class	0.30	day	850.00	255.00
2	Mazdoor (Unskilled)	2.20	day	550.00	1,210.00
3	Bhisthi	0.50	day	550.00	275.00
Labour Sub-Total:					1,740.00
III. MACHINERY / HIRE CHARGES					
1	Concrete Mixer 10/7 cft hire & fuel	0.50	hour	450.00	225.00
2	Needle Vibrator 40mm needle hire & fuel	0.50	hour	150.00	75.00
Machinery Sub-Total:					300.00
Basic Prime Cost for 1 cum:					5,807.50
Contractor Overhead & Profit (14%):					813.05
Lead Conveyance Charges Total:					373.50
Total Cost for 1 cum:					Rs. 6,994.05

Lead & Conveyance Breakdown:

Material	Lead Distance	Quantity	Lead Rate (Rs)	Amount (Rs)
Coarse Sand	18 km	0.45 cum	350.00	157.50
HBG Aggregate 20mm	12 km	0.90 cum	240.00	216.00
Total Lead Addition:				Rs. 373.50